SYNTHETIC SAMPLE - FICTIONAL MANUFACTURER - NOT FOR CONSTRUCTION

BESS Ventilation and Exhaust Plan - Century Tywood J3 Corp (synthetic)

Document No.: CTJ3-VENT-001

Revision: A

Date: 2026-11-06

Prepared for: Town of Holliston Fire Department plan review (synthetic)

Design basis

Enclosure: Gotion Edge 760 outdoor cabinet (synthetic)

Exhaust ventilation design: continuous mechanical exhaust with gas-detection interlock

Design exhaust rate: 1,200 CFM (synthetic value for demonstration only)

SYNTHETIC SAMPLE - FICTIONAL MANUFACTURER - NOT FOR CONSTRUCTION

Sequence of operation

1. Gas detector at 10% LFL starts exhaust fan EF-1 and alarms the FACP.
2. Fan failure is supervised and reported to the monitoring company.
3. Make-up air louver opens on fan start.

Engineer of record review required. Not a certification of code compliance.